



Republic of the Philippines  
**J.H. CERILLES STATE COLLEGE**  
 Brgy. Mati, San Miguel, Zamboanga del Sur  
 www.jhcscmain.edu.ph  
 Email add: jhcsc.main@yahoo.com

Project Title : Installation of Solar Street Light at JHCSC-Main Campus  
 Project Location : Mati, San Miguel, Zamboanga del Sur

<b>BILL OF QUANTITIES OF PROPOSED WORK</b>					
ITEM NO.	DESCRIPTION	UNIT	QTY	UNIT COST	TOTAL
803 (1)a	Structure Excavation (Common Soil)	cu.m.	35.20	<i>Amount in Words</i> <i>Amount in Figures</i>	<i>Amount in Words</i> <i>Amount in Figures</i>
804 ( 1 ) a	Embankment ( From Structure Excavation)	cu.m	24.20	<i>Amount in Words</i> <i>Amount in Figures</i>	<i>Amount in Words</i> <i>Amount in Figures</i>
804 (4)	Embankment ( Gravel Bedding )	cu.m.	2.96	<i>Amount in Words</i> <i>Amount in Figures</i>	<i>Amount in Words</i> <i>Amount in Figures</i>
900 (1)c2.1	Structural Concrete (Footings)	cu.m.	7.39	<i>Amount in Words</i> <i>Amount in Figures</i>	<i>Amount in Words</i> <i>Amount in Figures</i>
900 (1)c4	Structural Concrete (Pedestal)	cu.m.	11.09	<i>Amount in Words</i> <i>Amount in Figures</i>	<i>Amount in Words</i> <i>Amount in Figures</i>
902(1.1)	Reinforcing Steel (Deformed bar for Footings)	kgs.	411.18	<i>Amount in Words</i> <i>Amount in Figures</i>	<i>Amount in Words</i> <i>Amount in Figures</i>
902(1.4)	Reinforcing Steel (Deformed bar for Pedestal)	kgs.	619.08	<i>Amount in Words</i> <i>Amount in Figures</i>	<i>Amount in Words</i> <i>Amount in Figures</i>
1027(1)	Cement Plaster Finish	sq.m.	39.85	<i>Amount in Words</i> <i>Amount in Figures</i>	<i>Amount in Words</i> <i>Amount in Figures</i>
1032 (1)a	Painting Works (Concrete)	sq.m	35.20	<i>Amount in Words</i> <i>Amount in Figures</i>	<i>Amount in Words</i> <i>Amount in Figures</i>
1,047	Metal Structures (Tapered Pole)  6.0 Meters Tapered Pole, Material: Hot dip galvanized steel, Pole height: 6.0 Meters Tapered Pole, Top Dia.: 2.0 Inches, Bottom Dia.: 5.0 Inches, Thickness: 2.5mm, Pole base Plate: 300 x 300 x 10mm, Fordable Anchor bolt bending inside: 4 pcs x 16mm dia.	sets	44.00	<i>Amount in Words</i>  <i>Amount in Figures</i>	<i>Amount in Words</i>  <i>Amount in Figures</i>
SPL-1	Solar Street Light (ALL-IN-ONE SOLAR STREET LIGHT) System Power - 30W Luminous Flux- 6,000 lm Efficacy - 200 lumens/W Solar Panel- 30W (Mono-crystalline) Battery - 12.8V18Ah (230Wh)	sets	44.00	<i>Amount in Words</i>  <i>Amount in Figures</i>	<i>Amount in Words</i>  <i>Amount in Figures</i>
B.7	Construction Safety and Health Occupational	Month	3.00	<i>Amount in Words</i> <i>Amount in Figures</i>	<i>Amount in Words</i> <i>Amount in Figures</i>
B.5	Project Billboard	Each	1.00	<i>Amount in Words</i> <i>Amount in Figures</i>	<i>Amount in Words</i> <i>Amount in Figures</i>
<b>TOTAL</b>		<b><i>Amount in Words</i></b> <b><i>Amount in Figures</i></b>			